



- NOTES**
1. The property owner is responsible for any adjustment to structures including, but not limited to, manholes and water valves.
  2. Concrete temperature may not exceed 90°F.
  3. All sidewalk replacement must meet ADA requirements.
  4. Expansion material shall be bituminous fiber material or as approved by the Engineer.
  5. Contractor shall saw and remove barrier curb. If rollover curb exists, contractor may match back of curb or saw and replace rollover curb.
  6. Sidewalk shall be located 5 ft. behind the curb on new construction; or where appropriate to match existing conditions.
  7. Driveway must be paved from street pavement to property line (or to existing sidewalk); with 3000# Portland Cement concrete.
  8. A permit is required for making new curb opening and work on Right-of-Way.

## COMMERCIAL DRIVEWAY STANDARD

The City of End  
 401 West O. C. Barrett Road  
 End, Oklahoma 77022  
 Tele: (860) 234-0400 Fax: (860) 234-8946

Contact:  
 Christopher Gagnoni, Director of Engineering Services  
 Murali Katta, P.E., City Engineer



REVISIONS	Number	Date	Description

Project Number:	PS - 7
Project Location:	END, OKLAHOMA

Sheet Title:	COMMERCIAL DRIVEWAY STANDARD
Project Title:	CONCRETE DRIVEWAYS STANDARD



Date:	JULY 2020
Scale:	None
File:	H:\STDS\STREETS\DRIVEWAYS.DWG
Drawn By:	SY
Designed By:	SY
Approved By:	MK
Sheet:	